

16. (a) The component of the force of gravity exerted on the ice block (of mass  $m$ ) along the incline is  $mg \sin \theta$ , where  $\theta = \sin^{-1}(0.91/1.5)$  gives the angle of inclination for the inclined plane. Since the ice block slides down with uniform velocity, the worker must exert a force  $\vec{F}$  “uphill” with a magnitude equal to  $mg \sin \theta$ . Consequently,

$$F = mg \sin \theta = (45 \text{ kg}) \left( 9.8 \text{ m/s}^2 \right) \left( \frac{0.91 \text{ m}}{1.5 \text{ m}} \right) = 2.7 \times 10^2 \text{ N} .$$

- (b) Since the “downhill” displacement is opposite to  $\vec{F}$ , the work done by the worker is

$$W_1 = - (2.7 \times 10^2 \text{ N}) (1.5 \text{ m}) = -4.0 \times 10^2 \text{ J} .$$

- (c) Since the displacement has a vertically downward component of magnitude 0.91 m (in the same direction as the force of gravity), we find the work done by gravity to be

$$W_2 = (45 \text{ kg}) \left( 9.8 \text{ m/s}^2 \right) (0.91 \text{ m}) = 4.0 \times 10^2 \text{ J} .$$

- (d) Since  $\vec{N}$  is perpendicular to the direction of motion of the block, and  $\cos 90^\circ = 0$ , work done by the normal force is  $W_3 = 0$  by Eq. 7-7.

- (e) The resultant force  $\vec{F}_{\text{net}}$  is zero since there is no acceleration. Thus, it’s work is zero, as can be checked by adding the above results  $W_1 + W_2 + W_3 = 0$ .